Ashby



Scheme description

The Gresley - Moira 33 kV circuits are close to their firm capacity. The proposed reinforcement solution is to reinforce the 33 kV circuit between Gresley and Moira to facilitate connection at Ashby De La Zouch primary. Installation of two new 3-panel boards is also required.



Constraint Season Winter



Flexibility Product **Secure**



No flexibility requirement under Best View until 2027.

Constraint management timeline

2023 H1 Signposting2022 H2 Signposting

2022 H1 Signposting

2021 H2 Signposting

2021 H1 Signposting

2020 H2 Procurement

Estimated flex utilisation required per year (MWh):

	2023	2024	2025	2026	2027
BV					1.40
СТ					1.20
LTW			0.30	56.30	
ST					
SP					



