Ashby



Scheme description

The Gresley-Moira 33 kV circuits are close to their firm capacity. It is proposed to reinforce the 33 kV circuit between Gresley and Moira to facilitate connection at Ashby De La Zouch Primary. Installation of two new 3-panel boards is also required.



Constraint Season Winter



Flexibility Product **Secure**



Justification for decision

No flexibility requirement under any scenarios until at least 2025.

Constraint management timeline

2022 H2 Signposting
2022 H1 Signposting
2021 H2 Signposting
2021 H1 Signposting
2020 H2 Procurement
2020 H1 Procurement

Estimated flex utilisation required per year (MWh):

	2022	2023	2024	2025	2026
BV					
СТ					0.16
LTW					0.88
ST					
SP					



