Exeter Main

Scheme description

Fault level studies have shown that reinforcement of the busbars, isolators and earthing grid at Exeter Main GSP is required.

Justification for decision

Flexibility is not suitable to deal with this constraint as it is a fault level restriction.

Reinforcement Information

Completion Year 2025 Current Status Preliminary



Indian Queens

Scheme description

Fault level studies have shown that reinforcement of the busbars, isolators and earthing grid at Indian Queens GSP is required.

Justification for decision

Flexibility is not suitable to deal with this constraint as it is a fault level restriction.

Reinforcement Information

Completion Year 2026 Current Status Preliminary



