Hereford BSP



Scheme description

Hereford BSP is a site consisting of two 132/66 kV transformers (GT4 and GT5) fed via two 132 kV circuits from Port Ham GSP. For a fault outage on one of these transformers the other could be at risk of overloading. The conventional reinforcement solution is installing a third 132/66 kV transformer at Hereford.



Constraint Season
Winter



Flexibility Product **Secure**



Reinforcement scheduled to be completed in 2023. Flexibility procurement is ongoing to deal with the constraint in the interim and provide additional network security.

Constraint management timeline

2022 H2	Procurement
2022 H1	Procurement
2021 H2	Procurement
2021 H1	Procurement
2020 H2	Signposting
2020 H1	Signposting
2019 H2	Signposting

2019 H1 Signposting

Estimated flex utilisation required per year (MWh):

	2022	2023	2024	2025	2026
BV	23.34	73.22			
СТ	93.87	367.49			
LTW	88.15	309.22			
ST	11.75	23.64			
SP	5.51	9.98			



