Nottingham to Wollaton Road Tee



Constraint description

For an arranged or fault outage on the main 1A 33 kV busbar at Nottingham BSP the 33 kV circuit between Nottingham BSP and the Wollaton Road tee is projected to overload.

Reinforcement description

The rationalisation of Nottingham BSP could help alleviate this constraint. 33 kV circuit works will likely also be required at a later date.





Constraint Season Winter and Summer

Outage Type



Justification for decision No flexibility requirement under Best View until 2032.

Constraint management timeline 2024 H2 Signposting

Time to Reinforce: 3 years Constraint Type: Demand

Estimated flexibility volumes (MWh) per year under Best View:

2024	2025	2026	2027	2028	2029	2030	2031	2032	2033	2034
-	-	-	-	-	-	-	-	2 MWh	16 MWh	77 MWh



For more information see the The Nottingham Group 33 kV NDP report: https://www.nationalgrid.co.uk/dso/network-development-plan