Haverfordwest Primary



Constraint description

Haverfordwest primary transformers and the 33 kV circuits from Haverfordwest BSP overload for the loss of either.

Reinforcement description

Replace the transformers with 20/40 MVA units and the 11 kV board. The next stage reinforcement will be to reinforce the 33 kV circuits.





Outage Type N-1



No flexibility requirement under Best View until 2029.

Constraint management timeline 2024 H2 Signposting

Time to Reinforce: 2 years

Constraint Type: Demand

Estimated flexibility volumes (MWh) per year under Best View:

2024	2025	2026	2027	2028	2029	2030	2031	2032	2033	2034
-	-	-	-	-	4 MWh	90 MWh	278 MWh	595 MWh	1238 MWh	2315 MWh

