# **Cairns Road Primary**



## **Constraint description**

Cairns Road primary has four transformers, run split to have 2x2 transformer sections. For the loss of a transformer under this arrangement the remaining transformer overloads.

#### **Reinforcement description**

Transfer demand to other primaries, such as Stoke Bishop, with 11 kV reinforcement.





Outage Type N-1

## Justification for decision

No flexibility requirement under Best View until 2031.

Constraint management timeline 2024 H2 Signposting

Time to Reinforce: 3 years Constraint Type: Demand

# Estimated flexibility volumes (MWh) per year under Best View:

2024	2025	2026	2027	2028	2029	2030	2031	2032	2033	2034
-	-	-	-	-	-	-	0.4 MWh	3 MWh	10 MWh	31 MWh

