Lye BSP



Constraint management timeline

2024 H2 Signposting2024 H1 Signposting

Time to Reinforce: 3 years
Constraint Type: Demand

Constraint description Lye Bulk Supply Point (BSP) consists of three Grid Transformers (GTs); one of which is smaller than the other two. An N-1 outage of one of the larger transformers overloads the smaller unit. Reinforcement description Replace GT3 with a 15/30 MVA unit and carry out site checks allowing the existing grid transformers at Lye BSP to utilise their cyclic ratings.





Outage Type

Estimated flexibility volumes (MWh) per year under Best View:

2024	2025	2026	2027	2028	2029	2030	2031	2032	2033	2034
-	-	-	-	-	-	-	-	0.4 MWh	8 MWh	38 MWh

